

COMMONWEALTH OF VIRGINIA
UNIFORM WATER WELL COMPLETION REPORT

OWNER: TED MEGEE
ADDRESS: 7716 GUNSTON DR.
LORTON, VA 22079
PHONE: (703) 339-7049
LOCATION: WIDEWATER

TAX MAP ID#: _____
PERMIT#: W-02-55
WCB PERMIT: _____
VWCB ID: _____
COUNTY: STAFFORD

WELL CLASSIFICATION: IIIA: IIIB: XXX IIIC: IV.

WELL DATA

GENERAL INFORMATION:

DRILLING METHOD: ROTARY	DATE COMPLETED: 05/15/02	TOT. DEPTH: 200 FT.
DEPTH TO BEDROCK: _____	YIELD: 100 (GPM)	TEST LENGTH: 4 HRS.
STATIC LEVEL: 4	STBLZED LEVEL: 34	NATURAL FLOW: NO
WELL DISINFECTED: YES	TYPE USED: CHLORINE	AMT. USED: 50 PPM

CASING:

FROM: +1 TO: 159	FROM: 154 TO: 180	FROM: TO:
SIZE: 4.5" MAT'L: PVC	SIZE: 2" MAT'L: GLV.	SIZE: 2" MAT'L: GLV.
WEIGHT/SCHED: SDR 17	WEIGHT/SCHED: SCH. 40	WEIGHT/SCHED: SCH. 40

GRAVEL PACK:

FROM	TO	FROM	TO	FROM	TO
------	----	------	----	------	----

GROUT:

FROM: 0 TO: 50	FROM: 50 TO: 159	FROM: 159 TO: 200
BORE HOLE SIZE: 8"	BORE HOLE SIZE: 7-1/4"	BORE HOLE SIZE: 3-7/8"
TYPE: BENSEAL	TYPE: _____	TYPE: _____
METHOD: PRESSURE	METHOD: _____	METHOD: _____

WATER ZONES:

FROM: 180 TO: 200	FROM: TO:	FROM: TO:
MESH: 15 DIAM.: 2"	MESH: DIAM.:	MESH: DIAM.:

PRIVATE WELL: DOMESTIC XXXX AGRICULTURAL INDUSTRIAL

MONITORING


PUBLIC WELL: COMMUNITY NON-COMMUNITY

* DRILLERS LOG *

DEPTH	DESCRIPTION OF FORMATION OR SEDIMENT	REMARKS
0-25	TAN AND GRAY CLAY	
25-35	GRAY CLAY	
35-43	BLUE SAND	
43-80	GRAY CLAY	
80-125	BLUE SAND AND GRAVEL	
125-180	GRAY CLAY	
180-200	BLUE SAND	

I CERTIFY THAT THE INFORMATION CONTAINED HERE IS TRUE AND THAT THIS WELL WAS INSTALLED AND CONSTRUCTED IN ACCORDANCE WITH THE PERMIT AND FURTHER THAT THE WELL COMPLIES WITH ALL APPLICABLE STATE AND LOCAL REGULATIONS, ORDINANCES AND LAWS.

NAME: KING GEORGE DRILLING SERVICE, INC.
ADDRESS: 861 MACEDONIA LANE
COLONIAL BEACH, VA 22443
PHONE: (804) 224-9130

DRILLER'S SIGNATURE: 
DATE: MAY 15, 2002 REPRESENTING: CHARLES E. SMITH
VIRGINIA CONTRACTOR'S LICENSE NUMBER: 2701 023065A